

| | | | | | | | |
|---|---|-------------|-------------|------------------|---------------------------------|--------------|--------------------------|
| Ridgefield, CT - Water Pollution Control Authority | | | | | | | |
| Infiltration/Inflow Rehabilitation | | | | <u>Vendors :</u> | National Water Main Cleaning Co | | Lash Contracting, Inc. |
| Bid 10-13 ; Project # 09-01, closed 10/23/09 @ 11am | | | | | Canton, MA | | Latham, NY |
| ITEM DESCRIPTION | | | | EST. | UNIT | CONTRACT | UNIT |
| <u>NO.</u> | | <u>Qtny</u> | <u>Item</u> | | <u>PRICE</u> | <u>PRICE</u> | <u>PRICE</u> |
| 1 | REPLACE BUILDING CONNECTIONS: | | | | | | |
| 1.a | Replace building connection with 6-inch pipe | 2 | connections | | \$6,000.00 | \$ 12,000.00 | \$15,000.00 \$ 30,000.00 |
| 1.b | Replace building connection chimneys | 1 | chimneys | | \$6,000.00 | \$ 6,000.00 | \$12,000.00 \$ 12,000.00 |
| | | | | | | | |
| 2 | Rock excavation and disposal | 50 | cu. yd. | | \$50.00 | \$ 2,500.00 | \$35.00 \$ 1,750.00 |
| | | | | | | | |
| 3 | Calcium chloride for dust control | 300 | lbs. | | \$5.00 | \$ 1,500.00 | \$1.00 \$ 300.00 |
| | | | | | | | |
| 4 | Sewer cleaning and TV inspection | 12,600 | lin. ft. | | \$1.10 | \$ 13,860.00 | \$1.80 \$ 22,680.00 |
| | | | | | | | |
| 5 | Chemical treatment and root removal | 13,100 | lin. ft. | | \$1.00 | \$ 13,100.00 | \$1.50 \$ 19,650.00 |
| | | | | | | | |
| 6 | JOINT TESTING: | | | | | | |
| 6a. | Test joints in 6-in. sewer | 205 | joints | | \$20.00 | \$ 4,100.00 | \$10.00 \$ 2,050.00 |
| 6b. | Test joints in 8-in sewer | 2,750 | joints | | \$17.00 | \$ 46,750.00 | \$12.00 \$ 33,000.00 |
| 6c. | Test joints in 10-in sewer | 850 | joints | | \$17.00 | \$ 14,450.00 | \$12.00 \$ 10,200.00 |
| 6d. | Test joints in 12-in. sewer | 850 | joints | | \$20.00 | \$ 17,000.00 | \$13.00 \$ 11,050.00 |
| | | | | | | | |
| 7 | JOINT SEALING AND RETESTING: | | | | | | |
| 7a. | Sealing and retesting joints in 6-in. sewer | 100 | joints | | \$5.00 | \$ 500.00 | \$2.00 \$ 200.00 |
| 7b. | Sealing and retesting joints in 8-in. sewer | 1,400 | joints | | \$7.00 | \$ 9,800.00 | \$2.00 \$ 2,800.00 |
| 7c. | Sealing and retesting joints in 10-in. sewer | 430 | joints | | \$9.00 | \$ 3,870.00 | \$4.00 \$ 1,720.00 |
| 7d. | Sealing and retesting joints in 12-in. sewer | 425 | joints | | \$11.00 | \$ 4,675.00 | \$5.00 \$ 2,125.00 |
| | | | | | | | |
| 8 | SPOT REPAIRS: | | | | | | |
| 8a. | Spot repairs of 6-in. through 12-in. sewers utilizing chemical grout method | 83 | locations | | \$425.00 | \$ 35,275.00 | \$100.00 \$ 8,300.00 |
| 8b. | Spot repairs of 6-in. through 12-in. sewers utilizing rigid repair sleeve method | 2 | locations | | \$0.01 | \$ 0.02 | \$2,000.00 \$ 4,000.00 |
| 8c. | Spot repairs of 6-in. through 12-in. sewers utilizing short cured-in-place liner repair method | 43 | locations | | \$1,100.00 | \$ 47,300.00 | \$1,200.00 \$ 51,600.00 |
| 8d. | Additional footage for spot repairs of 6-in. through 12-in. sewers utilizing rigid repair sleeve method | 15 | lin. ft. | | \$0.01 | \$ 0.15 | \$200.00 \$ 3,000.00 |
| 8e. | Additional footage for spot repairs of 6-in. through 12-in. sewers utilizing short cured-in-place liner repair method | 70 | lin. ft. | | \$200.00 | \$ 14,000.00 | \$200.00 \$ 14,000.00 |
| 8f. | Reinstate lateral service connections | 6 | connections | | \$500.00 | \$ 3,000.00 | \$250.00 \$ 1,500.00 |
| | | | | | | | |
| 9 | CURED-IN-PLACE SEWER PIPELINE REHABILITATION (inversion method): | | | | | | |
| 9a. | Line 8-inch sewer | 550 | lin. ft. | | \$45.60 | \$ 25,080.00 | \$50.00 \$ 27,500.00 |
| 9b. | Line 12-inch sewer | 700 | lin. ft. | | \$57.15 | \$ 40,005.00 | \$60.00 \$ 42,000.00 |

| | | | | | | | |
|---|--|--------------|-------------------|------------------|---------------------------------|----------------------|------------------------|
| Ridgefield, CT - Water Pollution Control Authority | | | | | | | |
| Infiltration/Inflow Rehabilitation | | | | <u>Vendors :</u> | National Water Main Cleaning Co | | Lash Contracting, Inc. |
| Bid 10-13 ; Project # 09-01, closed 10/23/09 @ 11am | | | | | Canton, MA | | Latham, NY |
| ITEM DESCRIPTION | | | | EST. | UNIT | CONTRACT | UNIT |
| <u>NO.</u> | | <u>Qntty</u> | <u>Item</u> | | <u>PRICE</u> | <u>PRICE</u> | <u>PRICE</u> |
| 10 | TV inspection of lateral service connections | 50 | connections | | \$230.00 | \$ 11,500.00 | \$350.00 |
| 11 | Cut protruding lateral service connections | 41 | connections | | \$150.00 | \$ 6,150.00 | \$350.00 |
| 12 | SEAL AND RETEST LATERAL SERVICE CONNECTIONS: | | | | | | |
| 12a. | Seal and retest lateral service connections as specified | 145 | connections | | \$380.00 | \$ 55,100.00 | \$425.00 |
| 12b. | Seal and retest lateral service connections as directed by Engineer following TV inspection of lateral service connections | 15 | connections | | \$380.00 | \$ 5,700.00 | \$425.00 |
| 13 | Removal and disposal of debris material | 250 | cu. yd. | | \$1.00 | \$ 250.00 | \$150.00 |
| 14 | Allowance for the service of Uniformed Police Officers | 1 | Allowance | | \$40,000.00 | \$ 40,000.00 | \$40,000.00 |
| | | | | | | | |
| | | | Total Cost | | | \$ 433,465.17 | \$ 478,775.00 |
| | | | | | | | |
| | Addenda Acknowledged | | | | | Yes | Yes |
| | Bond included | | | | | Yes | Yes |
| | | | | | | | |
| | | | | | | | |
| | | | | | | | |
| | | | | | | | |